

SRIVIJAYA VISAKHA MILK PRODUCERS COMPANY LIMITED

CIN :UI5209AP2006PTC048708

An ISO 9001 & 22000 Certified Dairy

Regd.No.48708/05-06, (Visakha Dairy, Visakhapatnam -530012)

Lr.No. 509/SM(C&P)/AMC/ VD/V-4,

Dt.04/10/2025.

To,

Sir/ Gentleman,

Sub:-C&P Wing- Visakha Dairy- Visakhapatnam – Construction of Toilets near to RMRD section in Main Dairy, Visakhapatnam - Quotations - Reg.


@ @ @

You are requested to quote your lowest price for Construction of Toilets near RMRD section in Main Dairy, Visakhapatnam including all materials (Excluding cost of Cement & Steel which will be supplied by the dept) and labour charges for the works mentioned (Annexure & Drawings enclosed).

The Quotations should be addressed to the Managing Director, Sri Vijaya Visakha Milk Producers Company Limited, Opp. BHPV, Visakhapatnam-530012 and the same should reach this office on or before 08/10/2025 by 11.00 A.M.

Encl:-As above.

Yours faithfully,


(K.Srinivasa Rao)

Asst.General Manger,

Civil & Projects.

Contact No.0891-2517230, Ex-36.

ANNEXURE

Name of the Work :- Const. of Toilets near to RMRD Section in Main Dairy, Visakahapatnam.

(Excluding cost of Cement & Steel)

S. No	Description of the Work	Approx. Qty	Quoted Rate
1	Earthwork Excavation in hard gravelly soils, red earth, shales, morrum, ordinary gravel, Black cotton soils, loamy and clayee soils and all other types of soils except rock requiring Blasting in all conditions such as dry, wet and slushy & Depositing the soils on the banks with an initial lead of 10 Mtrs. and lift of 2 Mtrs. Depth including all incidental and operational charges etc., complete. as directed by the dept. during the execution work including bailing of water	12.00 Cum	
2	Supply and Filling of Crusher Dust including cost and conveyance of all material, incidental charges and operational charges, ramming, complete as directed by the dept.	6.00 Cum	
3	C.C.(1:4:8) Prop. using 40mm gauge HBG metal including cost and conveyance of all materials, labour charges, curing etc., complete. As directed by the dept. during the execution of work. Excluding cost of Cement which will be supplied by the dept.	5.00 Cum	
4	R R Masonry in CM(1:6)Prop. Using R.R. Stone for walls of all thickness including cost and conveyance of all material charges, all labour charges, Bond Stones, curing, racking the joints etc. complete. Excluding the cost of cement supplied by the dept.	12.00 Cum	
5	R.C.C(1:1/2:3) Prop. using 20mm gauge HBG graded Machine crushed Metal including cost and conveyance of all materials, labour charges, machine mixing, vibrating, finishing Centering, and curing etc., complete. as directed by the dept. during the execution of work. But excluding the cost of steel reinforcement of work & its fabrication charges which will be accounted separately for the following items of works. Excluding cost of Cement, supplied by the dept.		
a.	<u>RCC Plinth Beam</u>	4.00 Cum	
b.	<u>RCC Roof Beam</u>	1.70 Cum	
c.	<u>RCC Roof Slab</u>	5.00 Cum	

S. No	Description of the Work	Approx. Qty	Quoted Rate
6	Cutting, Bending and Fabrication of bars & Placing them in position of all sizes on Plain or ribbed & for all items of RCC works at all heights including cost and conveyance of all materials, labour charges etc., complete as directed by the dept. During the execution of work. for all items of RCC works of all heights, Excluding cost of Steel, Which will be supplied by the Dept. but including cost of binding wire	1,100.00 Kgs.,	
7	Supply and Filling of Gravel in Basement including cost and conveyance of all material, labour, incidental charges and operational charges, Consolidation, ramming, complete as directed by the dept.	15.00 Cum	
8	C.C(1:2:4) Prop. using 20mm gauge HBG Graded Machine crushed Metal including cost and conveyance of all materials, labour charges, finishing and curing etc., complete. as directed by the dept. during the execution of work. Excluding cost of Cement, supplied by the dept.	1.50 Cum	
9	Brick masonry in C.M (1:6) Prop. Using Light Weight Bricks for all walls of all thickness including cost and conveyance of all material, all labour charges, curing, racking the joints, scaffolding charges etc. Excluding cost of cement, which will be supplied by the dept.	18.00 Cum	
10	Plastering with CM(1:4) Prop. 20mm thick Single coat including cost and conveyance of all materials, labour charges, Scaffolding charges, curing, etc., complete. As directed by the dept. during the execution of the work. Excluding cost of Cement, Supplied by the dept.	190.00 Sqmt.	
11	Ceiling Plastering in CM(1:3) Prop. 1/2" thick in single coat with smooth finishing including cost and conveyance of all materials, labour charges, curing, scaffolding charges etc., complete. As directed by the dept. During the execution of work. Excluding cost of cement, which will be supplied by the dept.	55.00 Sqmt.	
12	Grading plastering with C.M(1:3) 1" thick mixed with water proofing compound including cost and conveyance of all material and all labour charges, curing, scaffolding charges, excluding cost of cement, which will be supplied by the dept.	40.00 Sqmt.	

GST

Note : The management reserves the right either to accept/ reject the teners without ascertaining any reasons

Signature of the Contractor

Construction of Ladies Toilet Slab Near RMRD Building

